



- NOTES:**
1. SITEWORK CONSTRUCTION TO BE PERFORMED IN COMPLIANCE WITH CONTRACT DOCUMENT TECHNICAL SPECIFICATIONS AND DESIGN DRAWINGS.
  2. REFER TO SHEETS M-3 AND M-4 FOR THE SITE DEVELOPMENT PLAN AND DETAILS.
  3. CONTRACTOR SITEWORK - ALL EXCAVATION, BACKFILL, GRADING, FOUNDATIONS, AND SURFACING MATERIAL REQUIREMENTS AND CONSTRUCTION TO BE PERFORMED BY THE CONTRACTOR.
  4. CITY SITEWORK - ALL HIGH VOLTAGE AND LOW VOLTAGE CONDUITS, GROUNDING, FENCE INSTALLATION, AND SPRINKLER SYSTEM RESTORATION TO BE PERFORMED BY THE CITY.
  5. ALL SITEWORK ACTIVITY TIMING MUST BE COORDINATED BETWEEN THE CONTRACTOR AND THE CITY. THE CONTRACTOR IS TO TAKE THE LEAD IN DEVELOPING A WRITTEN SITEWORK SCHEDULE, AND ALL ACTIVITY DATES MUST BE AGREED UPON AND APPROVED BY THE CITY.
  6. REFER TO SHEET M-17 FOR 15-KV CONDUIT SECTIONS.
  7. CONDUITS FOR FEEDER 5 AND FUTURE FEEDER 6 TO BE TERMINATED EAST OF HWY 11 AS DETERMINED BY CITY.
  8. FOR SUBSTATION EQUIPMENT ELEVATIONS AND SECTIONS SEE SHEET 4 AND 5.
  9. FOR SUBSTATION EQUIPMENT NOTES AND MATERIAL LIST SEE SHEET 6.

**CVO**  
**Electrical**  
**Systems, LLC**

BAR IS ONE INCH ON ORIGINAL DRAWING  
IF NOT ONE INCH ON SCALES ACCORDINGLY.

DRAWN: A. IRWIN	REVISION
CHECKED: PROJ. ENG.: J. WITKOWSKI	
DRAWING FILE: 903209-M2	
DATE: 3/18/05	
5/07	REVISD RECORD DRAWING
5/05	REVISD RECORD DRAWING
3/05	RECORD DRAWING
DATE	

MILTON-FREEMWATER  
CITY LIGHT & POWER

**MILTON SUBSTATION**  
**GENERAL ARRANGEMENT**

SHEET  
**M-2**