



City of Milton-Freewater
Request for Proposals
Freewater Park Court Fencing
Contract No. 309.6

Date of Issue: May 16, 2025

REQUEST FOR PROPOSALS

ADDENDUM #1

RFP Contract No:	Contract 309.6
RFP Title:	Freewater Park Court Fencing
RFP Issue Date:	May 9, 2025
Addendum No.	1
Addendum Issue Date:	May 16, 2025

The RFP identified above is hereby amended as follows:

1. The following is hereby changed in Section 1. General:

~~**Schedule A - Court Fencing:** Schedule A consists of a lump sum bid price to include pricing to supply all materials and the complete installation of new fencing around the new multi-use court of commercial-grade, galvanized chain link fencing. All fence posts shall be set at least three feet (3') below the surface and be set in concrete. All posts and open ends shall have caps. The fence shall consist of a bottom, middle, and top rail with the chain link fence attached to all rails and posts. Fence is to be nine (9) gauge x 2" mesh galvanized chain link. The framework is to be three inches (3") Sch 40 end (corner) posts, two inches (2") Sch 40 line posts, and 1-5/8" Sch 40 rails. Two corral-style entrances shall be constructed along with two built-in soccer goals (10' wide x 6' tall x 2' deep).~~

Schedule A - Court Fencing: Schedule A consists of a lump sum bid price to include pricing to supply all materials and the complete installation of new fencing around the new multi-use court of commercial-grade, galvanized chain link fencing. All fence posts shall be set at least three feet (3') below the surface and be set in concrete. All posts and open ends shall have caps. The fence shall consist of a bottom, middle, and top rail with the chain link fence attached to all rails and posts. Fence is to be nine (9) gauge x 2" mesh galvanized chain link. The framework is to be two and seven-eighths inches (2-7/8") Sch 40 end (corner) posts, two and three-eighths inches (2-3/8") Sch 40 line posts, and 1-7/8" Sch 40 rails. Two soccer goals/court entrances should be installed on the North and South ends of the court. There will be a ten-foot (10') by six and a half foot (6.5') opening framed with two and seven-eighths inch (2-7/8") posts. On the west side of the opening, a four-foot (4') fence should extend out from the fence and then turn ninety degrees (90°) and continue for 14 feet (14'). This will create an "L-shaped" entrance behind each soccer goal, with the entrance facing east.

~~Option A – 20-foot posts for lighting: Optional Bid Item A is for a lump sum bid for supplying and installing ten (10) posts to be furnished and installed with a minimum bury depth of four feet (4') and set in concrete with 20 feet exposed above ground surface, specifically for lighting is requested. Fence posts shall have caps. 20-foot posts would replace 10-foot posts at the four corners and three posts evenly spaced along the court's long side(s). The 20-foot posts would replace the 10-foot posts for these locations. See the attached diagram.~~

Option A – 20-foot posts for lighting: Optional Bid Item A is for a lump sum bid for supplying and installing ten (10) posts with and outside diameter (OD) of four inches (4" to be furnished and installed with a minimum bury depth of four feet (4') and set in concrete with 20 feet exposed above ground surface, specifically for lighting is requested. Fence posts shall have caps. 20-foot posts would replace 10-foot posts at the four corners and three posts evenly spaced along the court's long side(s). The 20-foot posts would replace the 10-foot posts for these locations. See the attached diagram.

2. The Bid Schedule has been revised. The new bid Schedule is included below.

BID SCHEDULE, C-309.6
2025 Freewater Park Court Fencing

Schedule A – Court Fencing

ITEM	Unit	Quantity	Amount
Materials and installation of fencing - shall include commercial grade, galvanized chain link fencing. All fence posts shall be set at least three feet (3') below the surface and be set in concrete. All posts and open ends shall have caps. The fence shall consist of a bottom, middle, and top rail with the chain link fence attached to all rails and posts. Fence is to be nine (9) gauge x 2" mesh galvanized chain link. The framework is to be two and seven-eighths inches (2-7/8") Sch 40 end (corner) posts, two and three-eighths inches (2-3/8") Sch 40 line posts, and 1-7/8" Sch 40 rails. Two soccer goals/court entrances should be installed on the North and South ends of the court. There will be a ten-foot (10') by six and a half foot (6.5') opening framed with two and seven-eighths inch (2-7/8") posts. On the west side of the opening, a four-foot (4') fence should extend out from the fence and then turn ninety degrees (90°) and continue for 14 feet (14'). This will create an "L-shaped" entrance behind each soccer goal, with the entrance facing east.	1	Lump Sum	\$

Option A –Posts for Lights

ITEM	Unit	Quantity	Amount
Supplying and installing ten (10) posts with and outside diameter (OD) of four inches (4") to be furnished and installed with a minimum bury depth of four feet (4') and set in concrete with 20 feet exposed above ground surface, specifically for lighting is requested. Fence posts shall have caps. 20-foot posts would replace 10-foot posts at the four corners and three posts evenly spaced along the court's long side(s). The 20-foot posts would replace the 10-foot posts for these locations. See the attached diagram.	1	Lump Sum	\$

Signature of Bidder's Authorized Agent

Date

NOTE TO BIDDERS: The City reserves the right to increase or decrease without restriction, the amount of any class of material or work that may be deemed necessary, and bidders shall submit balanced bids in order that they may not be affected adversely by increase or decrease in quantities.

3. The attached diagram has been updated. The new diagram is included below.

